ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಟಿಪ್ಪಣಿ ಹಾಳೆ

ವಿಷಯ Providing Basic Amenities ... ಪುಟದ ಸಂಖ್ಯೆ — 1 —

ವಾರ್ಡ್ No:08 Kodigenahalli ಕಡತದ ಸಂಖ್ಯೆ ಪಶ್ವಿ/ಯೋಜ-ಯ/ [illegible]

Security Arrangement for Non-SR items ಪಾಲಿ/ 87 /18-19

ಪಂಕ್ತಿಯ ಸಂಖ್ಯೆ	ಟಿಪ್ಪಣಿಗಳು ಮತ್ತು ಆಜ್ಞೆಗಳು

ಮಂಡಿಸಿದೆ:

ವಿಷಯ:- Providing Basic Amenities and Procurement of Dustbins in Ward No.08, Kodigenahalli-Regarding inviting Quotation for Non-SR Items. ಒದಗಿಸುವ ಅಂಶಗಳಿಗೆ ದರ ನಿಗದಿ ಪಡಿಸಿಕೊಳ್ಳಲು ಕೋಟೇಷನ್ ಆಹ್ವಾನಿಸಲು ಅನುಮತಿ ಕೋರುವ ಬಗ್ಗೆ.

*** *** ***

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ಬ್ಯಾಟರಾಯನಪುರ ವಿಧಾನ ಸಭಾ ಕ್ಷೇತ್ರದ ವಾರ್ಡ್ ನಂ:08ರ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ ಕಸದ ಕಪ್ಪು ರಂದ್ರದ ಜಾಗಗಳಲ್ಲಿ ಸಿಸಿ ಕ್ಯಾಮರಾ ಹಾಗೂ ಕಸದ ಬುಟ್ಟಿ ಒದಗಿಸಲು ಕಾಮಗಾರಿಗೆ 2017-18ನೇ ಸಾಲಿನ 14ನೇ ಹಣಕಾಸು ಅಯೋಗದ ಅಡಿಯಲ್ಲಿ ಪಿ-3110ರ ಅನುದಾನದಡಿ ರೂ.99.00 ಲಕ್ಷಗಳ ಅನುದಾನದಕ್ಕೆ ಅನುಮೋದನೆ ದೊರೆತ್ತಿರುತ್ತದೆ. ಅದರಂತೆ ಈ ಕೆಳಕಂಡ ಅಂಶಗಳಿಗೆ ದರ ನಿಗಧಿಪಡಿಸಬೇಕಾಗಿರುತ್ತದೆ.

Sl. No	Description / Specification
1	Supplying ,installation ,Commissioning and Testing CP PLUS 2 MP PTZ1/2.8" 2MP Exmor R CMOS Image sensor Max. 50/60fps@1080P, 25/30/50/60fps@720P,Powerful 25x Optical and 16x Digital zoom WDR(120dB), 3D DNR, Day/Night(ICR), BLC, HLC Up to 300 presets, 8 auto scan, 8 tour, 5 pattern, 8 auto pan IR Range of 150 Mtr. , IP66, Support PoE Plus Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
2	Supplying ,installation ,Commissioning and Testing CP PLUS 3 MP50 meters ip bullet camera,1/3" 3MP PS CMOS Image Sensor,Max 25fps@3MP, 25/30fps@1080P,H.264, H.264H, H.264B , MJPEG dual-codec encoding,DWDR, Day/Night(ICR), 3DNR, ROI, AWB, AGC, BLC, HLC,3.6mm fixed lens (6mm optional),IR Range of 50 Mtrs, IP67, SD Card, PoE,Mobile Software: ICMOB, gCMOB,CMS Software: KVMS Pro, vOptimus Pro inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
3	Supplying ,installation ,Commissioning and Testing CP PLUS 32 Ch. H.265 4K Network Video Recorder Up to 32 channel IP camera input H.265/H.264 dual codec decoding Up to 8Mp resolution preview and playback Max 200Mbps incoming bandwidth Support 4 SATA HDDs up to 24TB, 2 USB(1 USB3.0) HDMI / VGA simultaneous video output Support Multi-brand network cameras ONVIF Version 2.4 conformance Mobile Software: ICMOB, gCMOB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
4	Supplying ,installation ,Commissioning and Testing Netgear ReadyNAS 4-Bay Diskless Network Attached Storage for Personal Cloud by Netgear inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
5	Providing and Supplying NAS hard disk drives 6 TB inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
6	Supplying ,installation ,Commissioning and Testing D-Link 24-Port Gigabit Switch With 4 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
7	Supplying ,installation ,Commissioning and Testing D-Link 8-Port Gigabit Switch With 2 Combo SFP Ports inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
8	Providing and Supplying CAT6 OUT Door 305 mtr Cable Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge

ಪು.ತಿ.ನೋ

ಕ್ರಮ ಸಂಖ್ಯೆ	ವಿವರಗಳು ಮತ್ತು ಅಳತೆಗಳು
9	Providing and Fixing Media converter Giga Dlink Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
10	Providing and Fixing OFC cable single mode 6 core Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
11	Providing Cctv MS poles with camera fixing brackets, 5 to 6 mtr height Box Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
12	Providing and Fixing MS Boxes for Poles with rust proof powder coating Box Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
13	Providing and Fixing Electrical work for boxes for power supply, fixing PVC Boards with three pin socktes and switches with protection MCB and cabling to street light electrical poles as per the direction of Engineer in Charge
14	Providing Internet charges connecting CCTV with IP Based for one month
15	Providing and Fixing static IOP charger for ISP on each IP Address Box Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
16	Providing and Fixing SFP-LX-SM GIGA MODULE Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
17	Providing and Fixing Fibre Optic PATCH Chords Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
18	Supplying ,installation ,Commissioning and Testing UPS 2 KVA with two batteries Box inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
19	Erecting of pole .The pole shall be erected n cement concrete work(1:2:4) including earthwork excavation and refilling of planting depth of the pole to the ground level and the copping CC shall be upto 0.6m above ground level as per IS 2713-7.1 Erection of lightduty pole on footpath a) 7.5m as per IS 410 Sp 5 charges as per the direction of Engineer in Charge
20	Providing and Fixing HDMI Cables 10 Mtrs Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
21	Supplying ,installation ,Commissioning and Testing Video Manager Application Software for Display and Management of Camera on Video Display Box Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
22	Supplying ,installation ,Commissioning and Testing of 43" LED TV – Reputed make Sony/2amsung/LG Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
23	Supplying ,installation ,Commissioning and Testing Patch cords CAT6 2 Mtr Box Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
24	Supplying ,installation ,Commissioning and Testing Server rack 42u with all accessories and power supply Box Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
25	Supplying ,installation ,Commissioning and Testing Server rack 15u Box Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
26	Maintenance charges for one year for each camera
27	Supplying ,installation ,Commissioning and Testing of CPU - I 3 Processor - 450MHz, 8GB Ram, 250 Gb Hard Disk Full Core Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge
28	Supplying of dustbin for collection dry and wet waste for segreation , made up of plastic Inclusive of all taxes and transportation charges as per the direction of Engineer in Charge

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಟಿಪ್ಪಣಿ ಹಾಳೆ

ವಿಷಯ: Provid. basic Amenities in Engg. works ಪುಟದ ಸಂಖ್ಯೆ: -3-

ಇವರ ಪತ್ರ/ಜ್ಞಾಪನ ಸಂಖ್ಯೆ: Ward No. 08 - Yelahanka Town ಕಡತದ ಸಂಖ್ಯೆ: ಕೆ.ಗ/ಯೋಜ-ಯ/ಟಿಪ್ಪ

Quotation for Ward No-31 ನೇ ವಾರ್ಡ್ ದಿನಾಂಕ 87/18-19

ಪಂಕ್ತಿಯ ಸಂಖ್ಯೆ	ಟಿಪ್ಪಣಿಗಳು ಮತ್ತು ಆಜ್ಞೆಗಳು
2	ಈ ಮೇಲೆ ಅಂಶಗಳಿಗೆ ಕಾಮಗಾರಿಯ ಲೋಕೋಪಯೋಗಿ ದರಪಟ್ಟಿಯಲ್ಲಿ ದರಗಳು ಲಭ್ಯವಿಲ್ಲದ ಕಾರಣ ಹಾಗೂ ಸದರಿ ಅಂಶಗಳ ದರಗಳನ್ನು ಕೋಟೇಷನ್ ಮುಖಾಂತರ ನಿಗದಿ ಪಡಿಸಿಕೊಳ್ಳುವ ಅವಕಾಶವಿರುವುದರಿಂದ, ಸದರಿ ಅಂಶಗಳ ದರಗಳಿಗೆ ಯೋಜನೆ ವಿಭಾಗದಿಂದ ಅಲ್ಪಾವಧಿ ಕೋಟೇಷನ್ ಆಹ್ವಾನಿಸಲು ಅನುಮೋದನೆ ಕೋರಿ ಕಡತವನ್ನು ಮಂಡಿಸಿದೆ. ಸಹಾಯಕ ಅಭಿಯಂತರರು 31/10 ಸ.ಅ(ಯೋ.ವಿ) Executive Engineer 21/X/18 ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು, ಯೋಜನಾ ವಿಭಾಗ, ಯಲಹಂಕ ವಲಯ. Yelahanka Zone BBMP, Bangalore-92
3	ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು(ಯ.ವ) ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು (ಪ್ರಭಾರ) 31/10/18 ಯಲಹಂಕ ವಲಯ ಬೃಬೆಂಮಪಾ ಬೆಂಗಳೂರು-92
4	ಕಂಡಿಕೆ(3)ರಲ್ಲಿ ಮುಖ್ಯ ಅಭಿಯಂತರರು ಯಲಹಂಕ ವಲಯರವರು ಕೋಟೇಷನ್ ಆಹ್ವಾನಿಸಲು ಅನುಮೋದಿಸಿರುವುದರಿಂದ ದಿನಾಂಕ:21-10-2018ರಂದು ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು ಯೋಜನ ವಿಭಾಗದಿಂದ ಕೋಟೇಷನ್ ಕರೆಯಲಾಗಿದ್ದು, ದಿನಾಂಕ:28-10-2018 ರಂದು ಕೋಟೇಶನ್ ತೆರೆಯಲಾಗಿರುತ್ತದೆ, ಈ ಪ್ರಕ್ರಿಯೆಯಲ್ಲಿ ಮೂರು ಸಂಸ್ಥೆಗಳು ಕೆಳಕಂಡಂತೆ ಭಾಗವಹಿಸಿರುತ್ತಾರೆ. 1) M/s.QUALZEN SYSTEMS, 2) M/s.INTERSECT ENTERPRISES 3) M/s.IMPERIAL OFFICE SUYSTEM
5	ಮೇಲ್ಕಂಡ ಸಂಸ್ಥೆಗಳ ಪೈಕಿ M/s.QUALZEN SYSTEMS ರವರು ಅತೀ ಕಡಿಮೆ ದರಗಳನ್ನು ನಮೂದಿಸಿರುತ್ತಾರೆ(ತುಲನಾತ್ಮಕ ಪಟ್ಟಿಯನ್ನು ಕಡತದಲ್ಲಿ ಲಗತ್ತಿಸಲಾಗಿದೆ).
6	ಮೇಲಿನ ವಿವರಗಳನ್ನು ತಮ್ಮ ಅವಗಾಹನೆಗಾಗಿ ತರುತ್ತಾ ಸದರಿ ಕೋಟೇಶನ್ ಪ್ರಕ್ರಿಯೆಯಲ್ಲಿ ಅತೀ ಕಡಿಮೆ ದರಗಳನ್ನು ನಮೂದಿಸಿರುವ M/s.QUALZEN SYSTEMS ರವರ ದರಗಳನ್ನು ಅನುಮೋದಿಸಿ, ಸದರಿ ಕೋಟೇಶನ್ ದರಗಳು ಅಂದಾಜು ಪಟ್ಟಿಯಲ್ಲಿ ಅಳವಡಿಸಿಕೊಳ್ಳಲು ಅನುಮೋದನೆಗಾಗಿ ಕಡತವನ್ನು ಮಂಡಿಸಿದೆ. ಸಹಾಯಕ ಅಭಿಯಂತರರು 29/10 ಸ.ಅ(ಯೋ.ವಿ) Executive Engineer 29/X ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು, ಯೋಜನಾ ವಿಭಾಗ, ಯಲಹಂಕ ವಲಯ Project Division Yelahanka Zone BBMP, Bangalore-92
7	ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು(ಯ.ವ) ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು (ಪ್ರಭಾರ) 31/10/18 ಯಲಹಂಕ ವಲಯ ಬೃಬೆಂಮಪಾ ಬೆಂಗಳೂರು-92

ಪು.ತಿ.ನೋ